Items of work	Per	Quantity	Rate	Cost	Total
13. Gauge stones	Each	1			
14. Date stone	"	1			
15. Clearing jungle including removal of roots prickly pear and ant-hills, etc., and cutting trenches.	Each grade	24			
16. Baling water in trench	Lump sum				
17. Providing gravel backing behind revetment.	C.yds.	1992			
Total ...	...	...			
Constructing masonry sluice at R. L. 45·00 one at left and another at right of breaches.					
1. Earthwork cutting bund	C.yds.	49			
2. Surki concrete	C.ft.	286			
3. Burnt brick in surki mortar	"	888			
4. Burnt stone slabs dressed	S.ft.	358			
5. Surki plastering	Sqr.	9·67			
6. Providing locking arrangements ...	L. S.	...			
7. Clay filling to sides of masonry ...	C.yd.	10			
8. Cutting orifices	Each	3			
Total for one sluice ..	...	...			
For two sluices ...	...	...			
Left waste weir 95′ R. L. 53·00.					
1. Earthwork excavation for foundation chargeable to bund.	C.yd.	..			
2. Surki concrete	C.ft.	479			
3. Burnt stone in surki mortar sized stones ..	"	4,462			
4. Burnt stone slabs 6″ thick and dressed ..	S.ft.	580			
5. Providing joggles...	Each	35			
6. Cement pointing	Sqr.	15·10			
7. Burnt stone Sujeecut apron	C.yd.	351			
8. Jelly filling	"	422			
9. Clearing site	L. S.	...			
Total ...	...	...			
Right waste weir 150 feet long R. L. 53·00.					
1. Earthwork excavation chargeable to bund .	C.yd.	...			
2. Surki concrete	C.ft.	537			
3. Burnt stone in surki mortar	"	2,832			
4. Burnt stone slabs 6″ thick dressed ...	S.ft.	652			
5. Providing joggles	Each	40			
6. Cement pointing	Sqr.	11·10			
7. Rough stone work new	C.yd.	218			
8. Jelly filling	"	111			
9. Clearing site	L. S.	...			
Total ..	...	...			

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

MYSORE SPECIAL DIVISION.

Notice dated 24th November 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Special Division, Mysore, up to 17th December 1928, till 12 noon, for constructing outhouses and workshops attached to the Institute for Defectives in Mysore. An abstract of approximate quantities are given below. These quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. and 5 P.M. on the working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.—

Description of work	Unit of work	Rate per unit	
		In words	In figures

4. Each tender must be accompanied by a deposit of rupees five hundred (Rs. 500), in cash or Government Promissory Notes, State Loan Bonds at market rates or in Savings Bank Pass Book of the tenderer having that amount at his credit on that date as earnest money, and be superscribed "Tender for constructing outhouses and workshops attached to the Institute for Defectives in Mysore," in default of which tenders will be rejected.

5. The final acceptance of the tender will rest with the Chief Engineer, Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond: in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. No tender stating "percentage less than the lowest tender or as per estimated rates" will be accepted.

10. Once the tender has been accepted no claim for any concessions or higher rates will be entertained.

11. The work to be executed as per D. P. W. Specification.

12. The decision of the Chief Engineer in all matters, regarding measurements, rates etc., shall be final and legally binding.

Abstract.

Items of work	Quantity	Per	Rate			Remarks
			Rs.	a.	p.	
1. Earthwork, excavating foundation filling in basement watering and tamping complete ...	364	C.yds.				
2. Filling foundation with stone jelly concrete in mortar	3,391	C.ft.				
3. Filling foundation and basement with burnt brick in mortar	10,390	,,				
4. Superstructure in burnt brick in mortar ...	10,515	,,				
4 (*a*) Burnt stone slabs over basement 6" thick ...	458	S.ft.				
4 (*b*) Two line dressing for the exposed portions of slab	815	,,				
5. Arch work with burnt brick in mortar ...	104	C.ft.				
6. Burnt stone lintel slabs 6" thick roughly dressed and fixed	236	S.ft.				
7. Teakwood panelled doors with hinges, hooks, locks, etc., complete	1,058	,,				
8. Teakwood panelled windows with iron bars, hinges, hooks, etc., complete	1,002	,,				

	Items of work	Quantity	Per	Rate Rs.	a.	p.	Remarks
9.	Teakwood wrought and put up ...	748·01	C.ft.				
10.	Teakwood ornamental eaves board 9″ x 1″ ...	724	R.ft.				
11.	Roofing with Mangalore pattern first class Yelahanka tiles on teak reepers, etc., complete	114·78	Sqr.				
12.	Do Ridge tiles set in mortar ...	313	R.ft.				
13.	Zinc sheet for valleys 1½′ wide with teakwood planks below, complete	75	,,				
14.	Pucca terrace roofiing	324	Sqr.				
15.	British standard or Tata Steel girders and joists with one coat of antierosive paint and hoisting and fixing, complete ...	12	Cwts.				
16.	Teak arched terrace with kappi in chunam and two courses of flat tiles, etc., complete ...	3·25	Sqr.				
17.	Chunam mortar plastering ...	266·16	,,				
18.	Flooring with Kadappa slabs on 3″ concrete bed and cement pointing, complete ...	67·02	,,				
19.	Silicate painting two coats to doors and windows	82·45	,,				
20.	Wood oiling 2 coats for wood work ..	115 01	,,				
21.	Dwarf parapet wall as per design	64	R.ft.				
22.	Light cornice work do	65	,,				
23.	Chimney for smoke escape	L. S.	..				
24.	Chunam borders	130	,,				
24 (*a*)	White and colour washing 2 coats ...	266·00	Sqr.				
25.	Wire cut brick wall with ex-metal for every 3rd course and plastering, complete ...	132	S. ft.				

V. V. KARVE,
Executive Engineer.

KADUR DIVISION.

Abstract Notification dated 17th *November* 1928.

Attention of the Public is invited to the notification calling for tenders for Restoring Hariharpur Mutt building, published on pages 1387 and 1388 of Part VI of *Mysore Gazette*, dated 22nd November 1928. The last date for receiving tender is 17th December 1928, till 2 P.M. Earnest money Rs. 140.

B. KRISHNA RAO,
Executive Engineer.

MYSORE RAILWAYS.

MYSORE DIVISION (OPEN LINES).

Dated 28th November 1928.

Notice is hereby given that separate sealed tenders will be received at the Office of the Executive Engineer, Open Line Division, Railways, Mysore, any working day up to 2 P.M., on the 15th December 1928, from contractors who are willing to undertake the execution of the following groups of works at Mysore South Station near Central Workshops area, Mysore.

1st Group—Construction of Station Building and Platform Latrine.

2nd Group—Construction of Station Master's Quarters (one unit) and Menials Quarters (3 units).

3rd Group—Earthwork cutting inclusive of all soils and forming bank wherever necessary with spoil inclusive of all lead and lift.